

3.2 支線1 数量総活表 1/2

種 別	細 別	規 格	単位	数 量	摘要
土工					NO. 2. 0～NO. 5. 0 区間 小運搬
	床掘		m3	287. 1	
	基面整正		m2	320. 6	
	埋戻		m3	130. 6	
	表土埋戻		m3	0. 0	
	残土処分		m3	142. 0	287. 1- 130. 6/0. 9
	小運搬	30～50m	m3	128. 5	1NO. 2～1NO. 5 残土搬出
	小運搬	30～50m	m3	58. 5	1NO. 2～1NO. 5 埋戻土搬入
	CON撤去		m3	3. 5	
	石積撤去	空石積み	m3	26. 0	
	小運搬	30～50m	m3	26. 0	1NO. 2～1NO. 5 残土搬出
	残土処分		m3	26. 0	
水路工					
	1-1号L型水路				L=36. 2m
	コンクリート	18-8-25	m3	10. 19	
	型枠	小型構造物	m2	47. 13	
	基礎材	RC40t=150	m2	49. 23	
	目地材	t=10mm	m2	1. 02	
	止水版	CF200	m	6. 80	
	1号U型水路				L=96. 70m (33. 5+25. 0+38. 2)
	コンクリート	18-8-25	m3	28. 53	3. 0m3/10m
	型枠	小型構造物	m2	198. 31	
	基礎材	RC40t=150	m2	124. 89	
	目地材	t=10mm	m2	2. 86	
	止水版	CF200	m	19. 07	
	2号U型水路				L=68. 00m
	コンクリート	24-12-25	m3	35. 47	5. 2m3/10m
	型枠	小型構造物	m2	255. 27	
	基礎材	RC40t=150	m2	132. 60	
	目地材	t=10mm	m2	3. 55	
	止水版	CF200	m	23. 67	
	鉄筋	SD345 D13	kg	1, 807	26. 57kg×68. 0m

3.2 支線1 数量総括表 2/2

[illegible]

土 工 (支線1) 数 量 計 算 書 (1)

測 点	距 離	床掘			基面整正			埋戻			備 考
		断 面	平 均	数 量	断 面	平 均	数 量	断 面	平 均	数 量	
1NO.0 (NO.10+0.30)		0.8			1.3			0.3			
1NO.1	20.00	0.8	0.80	16.0	1.3	1.30	26.0	0.3	0.30	6.0	
1NO.2	20.00	1.8	1.30	26.0	2.0	1.65	33.0	0.9	0.60	12.0	
1NO.2+10.00	10.00	1.8	1.80	18.0	2.0	2.00	20.0	0.8	0.85	8.5	小運搬
1NO.3	10.00	2.3	2.05	20.5	2.0	2.00	20.0	1.2	1.00	10.0	小運搬
1NO.4	20.00	2.5	2.40	48.0	2.0	2.00	40.0	1.0	1.10	22.0	小運搬
1NO.5	20.00	1.7	2.10	42.0	2.0	2.00	40.0	0.8	0.90	18.0	小運搬
1NO.6	20.00	1.3	1.50	30.0	1.4	1.70	34.0	0.5	0.65	13.0	
1NO.6+10.00	10.00	1.1	1.20	12.0	1.4	1.40	14.0	0.6	0.55	5.5	
1NO.7	10.00	1.3	1.20	12.0	1.4	1.40	14.0	0.5	0.55	5.5	
1NO.8	20.00	1.0	1.15	23.0	1.4	1.40	28.0	0.5	0.50	10.0	
1NO.9	20.00	0.7	0.85	17.0	1.1	1.25	25.0	0.4	0.45	9.0	
1NO.10	20.00	1.1	0.90	18.0	1.1	1.10	22.0	0.5	0.45	9.0	
1NO.10+4.2	4.20	1.1	1.10	4.6	1.1	1.10	4.6	0.5	0.50	2.1	
1NO.12											
1NO.13											
1IP.25											
合 計	204.20			287.1			320.6			130.6	

土 工（支線1）数 量 計 算 書（2）

測 点	距 離	表土埋戻			CON撤去			石積撤去			備 考
		断 面	平 均	数 量	断 面	平 均	数 量	断 面	平 均	数 量	
1NO.0 (NO.10+0.30)											
1NO.1	20.00										
1NO.2	20.00										
1NO.2+10.00	10.00							0.0			
1NO.3	10.00							0.4	0.20	2.0	小運搬
1NO.4	20.00							1.0	0.70	14.0	小運搬
1NO.5	20.00				0.0			0.0	0.50	10.0	小運搬
1NO.6	20.00				0.1	0.05	1.0				
1NO.6+10.00	10.00				0.0	0.05	0.5				
1NO.7	10.00										
1NO.8	20.00				0.0						
1NO.9	20.00				0.1	0.05	1.0				
1NO.10	20.00				0.0	0.05	1.0				
1NO.10+4.2	4.20										
1NO.12											
1NO.13											
1IP.25											
合 計	204.20			0.0			3.5			26.0	

3.5 支線4 数量総活表 1/1

種 別	細 別	規 格	単位	数 量	摘要
土工					
	床掘		m3	109.4	
	基面整正		m2	104.2	
	埋戻		m3	47.4	
	表土埋戻		m3	7.5	
	土砂等運搬		m3	49.2	109.4- 47.4/0.9-7.5
	CON撤去		m3	2.5	
	石積撤去		m3	0.0	
水路工					
	1号U型水路				L=89.49m
	コンクリート	18-8-25	m3	23.97	2.68m3/10m
	型枠	小型構造物	m2	183.63	
	基礎材	RC40t=150	m2	99.33	
	目地材	t=10mm	m2	2.40	
	止水版	CF200	m	16.00	
	2号U型水路				L=4.70m
	コンクリート	24-12-25	m3	1.81	3.85m3/10m
	型枠	小型構造物	m2	16.98	
	基礎材	RC40t=150	m2	5.22	
	目地材	t=10mm	m2	0.18	
	止水版	CF200	m	1.20	
	鉄筋工	SD345 D13	kg	76.61	16.3kg*4.7m
仮設道路					
	仮設道路		m	122.0	95.0+27.0
	敷き鉄板	1524*3048*22	枚	80.0	122.0/1.524
			m2	371.6	80*1.524*3.048
			t	64.2	80*0.802

土 工（支線4）数 量 計 算 書（1）

測 点	距 離	床掘			基面整正			埋戻			備 考
		断 面	平 均	数 量	断 面	平 均	数 量	断 面	平 均	数 量	
4NO.0 (1IP.20)		1.1			1.1			0.5			
4NO.1	20.00	1.1	1.10	22.0	1.1	1.10	22.0	0.5	0.50	10.0	
4NO.1+10.00	10.00	1.3	1.20	12.0	1.1	1.10	11.0	0.5	0.50	5.0	
4NO.2	10.00	1.3	1.30	13.0	1.1	1.10	11.0	0.5	0.50	5.0	
4NO.3	20.00	1.0	1.15	23.0	1.1	1.10	22.0	0.5	0.50	10.0	
4NO.4	20.00	1.1	1.05	21.0	1.1	1.10	22.0	0.5	0.50	10.0	
4EP	14.72	1.4	1.25	18.4	1.1	1.10	16.2	0.5	0.50	7.4	
合 計	94.72			109.4			104.2			47.4	

土 工（支線4）数 量 計 算 書（2）

測 点	距 離	表土埋戻			CON撤去			石積撤去			備 考
		断 面	平 均	数 量	断 面	平 均	数 量	断 面	平 均	数 量	
4NO.0 (1IP.20)		0.1			0.0						
4NO.1	20.00	0.1	0.10	2.0	0.0						
4NO.1+10.00	10.00	0.1	0.10	1.0	0.1	0.05	0.5				
4NO.2	10.00	0.1	0.10	1.0	0.1	0.10	1.0				
4NO.3	20.00	0.0	0.05	1.0	0.0	0.05	1.0				
4NO.4	20.00	0.1	0.05	1.0	0.0						
4EP	14.72	0.1	0.10	1.5	0.0						
合 計	94.72			7.5			2.5			0.0	